


Situation

RUBICON"

Situation

- The Republican River's storage reservoirs hadn't filled to adequate levels, resulting in the inability to deliver consistent flows to farmers.
- FCID had a 7-day ordering schedule, due to the travel time required from the reservoir to the diversion dam.
- Resulting in irrigators having to change crops, fallowing plots, growing crops under stress and using supplemental wells





RUBICON"

Initial steps for modernization

- Investing in distribution infrastructure improvements since the early 1980s, by converting smaller lateral canals to buried piped systems
- Several points in the system were also fitted with SCADA to better monitor and control flows at specific locations



3

Implementing automation

FCID decided to implement technology to automate the distribution system, including;

- Installed water-tight, solar powered, automated flow control gates enabling precise and continuous flow measurement
- Operated as an interconnected network of nodes, utilising distributed control architecture and a dedicated communication system.
- In addition, irrigation management software to enable remote operation, realtime network monitoring and demand planning tools.








Early Modernisation Outcomes



Early outcomes of the Cambridge Canal Modernization

- Frenchman Cambridge undertook the first stage investment of \$1.5 Million in 2016, and saw demonstrated savings better than 2,800 ac-ft per year
- Water recovered at less than \$20 per acre-foot
- Based on the success, the second phase was installed to recover an additional 1,400 ac-ft, totalling another \$0.9M



5

5

Automated Network Control



On-demand supply enabled by installing interconnected control and measurement technology into existing canals and pipeline infrastructure.



6

